



1. REMOVE ALL COATING 1" AROUND CUT-OUT. MASK EXISTING FOAM TO PROTECT FROM OVERSPRAY. LAP NEW COATINGS ONTO OLD COATING MIN 2".
2. NEW SPRAYED POLYURETHANE INSULATION (TECH GUARD)
3. TECH GUARD COATING SYSTEM
4. EQUIPMENT CURB BY OTHER
5. EXISTING FOAM ROOFING SYSTEM
6. ROOF DECK
7. TAPER 4" TO 6"
8. OLD BUR



EQUIPMENT BASE FLASHING (dwg. 41)

3003 North 73rd Street, Scottsdale, AZ 85251
 402 East Grand Road, Tuscon, AZ 85705

DRAWN BY:	DATE:	APPROVED:
SCALE:	PROJECT NO:	DRAWING NO.