



1. OVERFLOW OPENING IN SCUPPER RECIEVER BOX (TYPICAL)
2. DOWNSPOUT STRAPS (TYPICAL)
3. WALL (TYPICAL)
4. SUBSTRATE
5. MINIMUM 1/2"-3/4" TURNDOWNIN SCUPPER BOX INTO RECIEVER. SEAL AROUND LINER TO RECIEVER BOX WITH URETHANE CAULKINGS
6. SPRAYED POLYURETHANE INSULATION (TECH GUARD)
7. TECH GUARD COATING SYSTEM
8. SCUPPER BOX CONTINUOUS THROUGH WALL WITH MINIMUM 4" DECK AND WALL FLANGE (TYPICAL)



SCUPPER THROUGH WALL (dwg. 47)

3003 North 73rd Street, Scottsdale, AZ 85251
402 East Grand Road, Tuscon, AZ 85705

DRAWN BY:

DATE:

APPROVED:

SCALE:

PROJECT NO:

DRAWING NO.