



1. BEND TABS AFTER INSTALLATION & SCUPPER TO LEADER CAN
2. 22 GA. G.I. SCUPPER APPLIED DIRECTLY TO ROOF DECK
3. PROVIDE 5" X 15" OVERFLOW WITH 2" PROJECTION TO OUTSIDE. BOTTOM EDGE OF OVERFLOW TO BE 2" ABOVE ROOF LINE



**SCUPPER THROUGH WALL (ISOMETRIC)**  
(dwg. 48)

3003 NORTH 73RD STREET, SCOTTSDALE, AZ 85251  
402 EAST GRAND ROAD, TUCSON, AZ 85705

DRAWN BY:

DRAWN BY:

APPROVED:

SCALE:

PROJECT NO:

DRAWING NO: